7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yds.	20,696
Clearing silt, removing boulders and re-filling the same with new earth.	,,	19,000
Baling waters	Lump sum.	
Fixing old and new grade stone	Do	
Rough stone, new	C. yds.	3,368
Do old	,,	200
Turfing	S. yds.	12,188
Gravel backing	C. yds.	1,122
Sluices—		
Repairing 1, 2 and 3 sluices	Lump sum.	
Building a sluice in right weir in place of No. 4 sluice ...	Do	
Waste weirs—		
Waste weir, right, 350 feet long —		
Earthwork	C. yd.	5,834
Concrete in surki mortar	C. ft.	2,049
Brick in surki mortar	,,	4,541
Stone slabs	Sq. ft.	895
Jelly packing	Lump sum.	
Burnt stone in surki mortar	C. ft.	1,080
Burnt stone, dry, new	C. yds.	204
Do old	,,	200
Rough stone, new	,,	15
Plastering with chunam	Sq.	16·00
Pointing with chunam	,,	7·00
Waste weir, left, 450 feet long—		
Earthwork	C. yds.	1,191
Concrete in surki	C. ft.	1,603
Brick in surki	,,	4,612
Burnt stone in surki	,,	1,884
Burnt stone slabs 6" thick	S. ft.	860
Burnt stone, dry	C. yds.	1760
Rough stone, new	,,	60
Plastering with chunam	Sq.	20·00
Pointing with chunam	,,	10·00
Dismantling a portion of the existing weir to join in the new proposed extension.	Lump sum.	
Clearing approaches and draft	Do	

S. RAMASWAMI,
for *Executive Engineer.*

HASSAN DIVISION.

Dated 8th December 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 3rd January 1905, for restoring Kattarigatta tank Registered No. 72—113 of Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan, between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kattarigatta tank, Registered No. 72—113, of Channarayapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities for restoring Kattarigatta tank, Registered No. 72—113, Channarayapatna Taluk.

Items of works.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yd.	14,014
Turfing	S. yd.	10,877
Removing and re-fixing grade stones	Each.	29
New Index stones	,,	29
B. M. stones	,,	2
Registered number stone	,,	1
Date stone	,,	1
Gauge stone	,,	2
Rough stone work, new	C. yd.	2,344
Do old	,,	703
Gravel backing	,,	1,232
Sluice—		
Blocking up the old left sluice and constructing new one	Lump sum.	
Waste Weir left—		
Earthwork	C. yd.	59
Burnt brick in surki mortar	C. ft.	601
Burnt stone slabs	S. ft.	135
Plastering with surki mortar	Sqr.	2·90
Dry stone in chunam	C. ft.	160
Rough stone work, old	C. yd.	87
Do new	,,	53
Jelly filling under apron	,,	66
Earthwork ramp	,,	26
Turfing	Sqr.	7·00
Waste Weir right—		
Earthwork	C. yd.	59
Burnt brick in surki mortar	C. ft.	787
Burnt stone slabs	S. ft.	203
Plastering with surki mortar	Sqr.	3·42
Rough stone, work new	C. yd.	50
Earthen ramp	C. yd.	33
Turfing	Sqr.	18·00
Constructing silt dams—		
No. i—Earthwork	C. yd.	294
Rough stone work	,,	143
Jelly filling	,,	56
No. ii—Earthwork	,,	260
Rough stone work	,,	138
Jelly filling	,,	97
No. iii—Earthwork	,,	44
Rough stone work	,,	53

C. A. MAHADEVA SASTRI, *Executive Engineer.*

SHIMOGA DIVISION.

Notice dated 10th December 1904.

The 2nd class travellers' bungalow at Augumbi is closed for the public till further notice as the roof of the bungalow is burnt on the night of 6th instant.

K. KRISHNIENGAR, *Executive Engineer.*

KADUR DIVISION.

Notice.

The public is hereby informed that the travellers' bungalow at Balehole in Mudgere Taluk of Kadur District, is not available for occupancy.

Notice.

The attention of the public is invited to the notification in the Gazette of 8th instant calling for tenders for the work of constructing a masonry bridge of 5 arches of 50 feet span across the Bhadra river at Magundi, Koppa Taluk.

H. J. MOLLOY, *Executive Engineer.*